



# SRF Cryomodules for PIP-II at Fermilab

Genfa Wu

System Manager for SRF and Cryogenics

3-Jul-2019

SRF2019

In partnership with:

India/DAE

Italy/INFN


UK/STFC

France/CEA/Irfu, CNRS/IN2P3

# Outline

- Introduction
- Design Overview
- Technical Challenges
- Recent Progress
- Summary

# LBNF / DUNE / PIP-II



Long Baseline Neutrino Facility (LBNF) is the facility for the Deep Underground Neutrino Experiment (DUNE), a dual-site experiment for neutrino science and proton decay studies.

- Hosted at Fermilab (Batavia, IL) and SURF (Lead, SD)

The facility is an internationally designed, coordinated and funded program, a first of its kind for the US DOE.



# P5 Report defines PIP-II Mission



***PIP-II will enable the world's most intense beam of neutrinos to the international LBNF/DUNE project, and a broad physics research program, powering new discoveries for decades to come.***

## **PIP-II linac will provide:**

### **Beam Power**

- Meeting the needs for the start of DUNE (1.2 MW proton beam)
- Upgradeable to multi-MW capability

### **Flexibility**

- Compatible with CW-operations which greatly increases the linac output
- Customized beams for specific science needs
- High-power beam to multiple users simultaneously


### **Reliability**

- Fully modernizing the front-end of the Fermilab accelerator complex




***Building the world's most powerful neutrino beam cost-effectively***


# PIP-II at Fermilab Site



# PIP-II Project Scope



# PIP-II Project Scope



## 800 MeV H<sup>-</sup> linac

- Warm Front End
- CW SRF section

## Linac-to-Booster transfer line

- 3-way beam split

## Upgraded Booster

- 20 Hz, 800 MeV injection
- New injection area

## Upgraded Recycler & Main Injector

- RF in both rings

## Conventional facilities

- Linac tunnel includes 2 empty slots
- Upgrade capability to 1GeV





# PIP-II Project Scope

## 800 MeV H<sup>-</sup> linac

- Warm Front End
- CW SRF section


## Linac-to-Booster transfer line

- 3-way beam split




A. Saini et al., MOP033

# PIP-II Technical Driven Schedule (Draft)




# PIP-II SRF Linac & Areas of International Interest




# In-kind Contribution (Cryomodule Components)

Item	US DOE	In-kind
HWR Cryomodule	ANL builds cryomodule, FNAL tests.	
SSR1 Cryomodules	FNAL builds and tests all Cryomodules	<ul style="list-style-type: none"><li>• Some prototype cavities</li><li>• Production cavities, tuners and solenoids</li></ul>
SSR2 Cryomodules	FNAL builds and tests all Cryomodules	<ul style="list-style-type: none"><li>• Some prototype cavities</li><li>• Production cavities, tuners and solenoids</li></ul>
LB650 Cryomodules	FNAL tests all cryomodules	Prototype and production cryomodules including all sub components
HB650 Cryomodules	<ul style="list-style-type: none"><li>• FNAL builds prototype cryomodule and transportation tests</li><li>• FNAL tests all cryomodules</li></ul>	<ul style="list-style-type: none"><li>• Production cryomodules including all subcomponents</li><li>• Transportation design</li></ul>
Cryoplant	FNAL installation, integration and commissioning	Cryoplant Procurement
Cryogenic Distribution	FNAL design, procurement, installation and commissioning	


# Design Overview – Cavities




HWR




SSR1





SSR2



LB650




HB650



Preliminary Design  
Completed

# Design Overview – Cavities



Cavity	$\beta$	Frequency [MHz]	Aperture [mm]	Effective Length [mm]	Accelerating Gradient [MV/m]	$E_{\text{peak}}$ [MV/m]	$B_{\text{peak}}$ [mT]	R/Q [ $\Omega$ ]	G [ $\Omega$ ]
HWR	0.11	162.5	33	20.7	9.7	44.9	48.3	272	48
SSR1	0.22	325	30	20.5	10	38.4	58.1	242	84
SSR2	0.47	325	40	43.8	11.4	40	64.5	297	115
LB650	0.61	650	88	70.3	16.9	40.3	74.6	341	193
HP650	0.63	650	118	106.1	18.8	38.9	73.1	610	260

M. Bertucci, et al., MOP057


R. Paparella, et al., MOP060

M. Parise, TUP014

P. Berrutti, TUP066



# Design Overview – Cryomodules




HWR




SSR1



SSR2



LB650



HB650

Cryomodule	CM #	Cavity #	String Assy.	CM Length [m]	$Q_0 @ 2K$ [ $\times 10^{10}$ ]	$R_s [\Omega]$	$Q_L [\times 10^6]$
HWR	1	8	8 x (SC)	5.93	0.5	9.6	2.3
SSR1	2	8	4 x (CSC)	5.3	0.8	14	3.0
SSR2	7	5	SCCSCCSC	6.5	1.0	14.4	5.1
LB650	9	4	CCCC	5.52	2.2	9.0	10.4
HB650	4	6	CCCCCC	9.92	3.0	8.7	9.9

23 Cryomodules + 4 Prototypes


C = Cavity, S = Solenoid



# Design Overview – Cryomodules Standardization

Except HWR

- All cryomodules have cavities supported by room temperature strong back.
  - Same size of thermal shield, support post and vacuum vessel.
  - Same tooling and assembly procedure.
- 
- SSR1/SSR2 common design and components
  - LB650/HB650 common design and components




V. Roger et al., MOP094

# Design Overview – Cryomodules

All cryomodules have the same layout and the same pressure design values.


All cryomodules need to be compatible with a fast cool down:

- Above 20 K/hour through the Q-disease regime 90 - 175 K.
- Above 120 K/hour through the superconducting transition at 9.2 K



V. Roger et al., MOP094

# Cryomodule (CM) Development Path



# Technical Challenges – Cryomodule Heat Loads

- The Cryoplant design is dominated by the 2K heat load
- The 2K heat load is dominated by cavity performance
- Cavity heat loads are based on the expected CM installed  $Q_0$  factors and operating gradient

	HWR	SSR1	SSR2	LB650	HB650
Nominal Cavity $Q_0$ [-]	5E+9	8.2E+09	1.0E+10	2.2E+10	3.0E+10
Nominal Gradient [MV/m]	9.7	8.6	11.4	15.6	18.7
Cavities per CM [-]	8	8	5	4	6
Number of CMs [-]	1	2	7	9	4
<b>Dynamic per CM [W]</b>	<b>11</b>	<b>16</b>	<b>48</b>	<b>64</b>	<b>128</b>
<b>Static per CM [W]</b>	<b>27</b>	<b>18</b>	<b>14</b>	<b>7</b>	<b>9</b>

\*See ED0008200 for detailed individual cavity parameters

# Cryoplant Capacity Safety Factors

- Safety factors, representing the heat load uncertainty are explicitly defined to avoid mis-sizing
- Under-sizing leads to expensive upgrades or lower operating energy
- Over-sizing can lead to operational issues of capacity control, inefficiencies and unnecessary higher costs

$$Q_C = F_O(F_S Q_S + F_D Q_D)$$

$F_S = 1.3$ , static heat load safety factor

$F_D = 1.15$ , dynamic heat load safety factor

$F_O = 1.1$ , operational safety factor

## Heat Load Summary:

	2K (isothermal)	2K (non-isothermal)	5K (LTTS)	40K (HTTS)
CM Dynamic [W]	1466	0	407	1081
CM Static [W]	274	0	684	3156
CDS [W]	0	250	134	1971
Total Nominal [W]	1740	250	1225	6208
<b>Total with SF [W]</b>	<b>2244</b>	<b>358</b>	<b>1685</b>	<b>8699</b>

# R&D Goal of Cavity Q<sub>0</sub>

Cryomodule	2K Q0 Specification	2K Dynamic Heat Load Spec (W)	2K Q0 R&D Goal	2K Dynamic Heat Load R&D Goal (W)
HWR	5.0e9	11		
SSR1	8.3e9	32	1.0e10	28
SSR2	1.0e10	337	1.5e10	239
LB650	2.2e10	528	3.0e10	398
HB650	3.0e10	512	4.0e10	387

Improvement of 359 W



ED0008200 PIP-II Cryogenic Heat Load

R&D Supported both by Fermilab and partner labs

# Technical Challenges – CW High Power Couplers

## Coupler Design Goals (2 mA CW)

Cavity	Accelerating Gradient [MV/m]	Power Required [kW]	Power Designed [kW]	$Q_L$ [ $\times 10^6$ ]
HWR	9.7	5	10	2.3
SSR1	10	4.6	25	3.0
SSR2	11.4	13.5	25	5.1
LB650	16.9	30	55	10.4
HB650	18.8	44	55	9.9



S. Kazakov et al., MOP080


# Technical Challenges – Resonance Control

Initial needs – pulsed beam. Future needs – CW Beam. May operate initially with CW RF and pulsed beam, but exploring pulsed RF for cost saving in operation. Challenges for resonance control!

Cavity	LFD [Hz/(MV/m) <sup>2</sup> ]	Nominal LFD [Hz]	Half Bandwidth [Hz]
HWR	1.5*	-122	35
SSR1	4.4*	-440	54
SSR2	2.8	-362	32
LB650	1.7	-520	32
HB650	1.0	-352	33

\* Measured



- LLRF Development
- Increase bandwidth
- Increase tuner stiffness



TUP082, TUP083, TUP084, THP090


# Technical Challenges – Overseas Transportation

- 13 Cryomodules transport from overseas partner labs to Fermilab
- Transportation is part of the cryomodule prototyping
- Two dummy tests
  - From Fermilab to oversea partner lab
  - From oversea partner lab to Fermilab
- Three prototype cryomodules to be extensively tested
  - HB650 pCM from Fermilab to oversea partner lab
  - HB650 pCM from oversea partner lab to Fermilab
  - LB650 pCM from oversea partner lab to Fermilab




MOP089, MOP091, MOP094

# Recent Progress – Cavities



- ★ PIP-II 650 MHz R&D Goal
- ★ PIP-II 650 MHz Spec

2/6 doped B9AS-RRCAT-301 showed record breaking performance with Quench field >25 MV/m




Cavity B9A-AES-008 vertical testing showed cavity has very high quality factor of  $5\text{e}10$  at 20 MV/m.

M. Martinello, et al., MOP038



# Recent Progress – Couplers

- 650 MHz Coupler reached 50 kW CW
  - 55 kW Design goal
  - Limited by test stand, not by couplers. Improvement identified.
- Exceeds the requirement of dressed cavity integrated test in STC (Spoke Test Cryostat, a PIP-II horizontal test cryostat for both spoke and 650 MHz dressed cavities).



S. Kazakov et al., MOP080

# Recent Progress – Cryomodules




# Recent Progress – Cryomodules



HWR cryomodule cold mass assembly

**MOP101, MOP102, TUP095, THP090, THP091**



SSR1 cryomodule cold mass assembly



# Lessons Learned

- Lessons Learned from other Projects
  - Transportation by design
  - Comprehensive fastener torque specification
  - Studying microphonics early
  - Attention to magnetic field trapping during cryomodule test
  - Quality Engineer assigned to SRF Systems
- Lessons Learned within PIP-II
  - Improvement of assembly traveler
    - Spoke cavity S104 had a near-miss of uncontrolled pump down



D. Passarelli et al., TUP095

# Summary

- PIP-II SRF development is pushing the state of art to meet the needs of intensity frontier program at Fermilab.
  - PIP-II is the highest energy CW SRF proton linac in the world
  - PIP-II has attracted interest from Partner labs for in-kind contributions.
- Cryomodule development plan allows sufficient prototyping to feedback to production.
- Technical risks and challenges are mostly understood
- Lessons learned from other projects benefits PIP-II
- Significant progress has been made on all fronts
  - First two cryomodules nearing completion – RF testing in the fall.
- We thank all the partner labs for their contributions !



Thanks for your attention.

Questions ?

# Why a new Accelerator?

3 Nobels in last 30 years:  
1988: discovery of muon neutrino  
1992: discovery of neutrino  
2002: cosmic neutrinos

- Neutrinos: most ubiquitous matter particle in the universe, yet the least understood
  - Elementary particles with smallest mass of known particles
    - < one millionth that of the electron
  - ‘neutrino’ - electrically neutral and so small (mass)
  - typically pass through matter unimpeded & undetected
  - come in three flavors: electron, muon, tau
  - neutrinos oscillate between different flavors in flight
  - parameters of the oscillations still not completely understood
    - could unlock our understanding of the universe!
  - been a focus of physics at Fermilab since the beginning
- Current focus on the oscillations: short baseline (detectors on site) and long baseline (detectors in Minnesota and South Dakota)

